ADBRI Cement
ABN 96 007 870 199

# Cement Test Certificate

Final

62 Elder Road, Birkenhead SA 5015
PO Box 77, Port Adelaide SA 5015
T: +61 8 8300 0300
F: +61 8 8341 1591
www.adbri.com.au

**Product Certified:** Type GB General Blended Cement
**Test Certificate Number:** 260340
**Customer:** Adbri Cement, Birkenhead Plant, SA
**Sample Code:** B0c7aca
**Sample Date:** 15/05/2026

| Nominal Blend | Requirements | Result |
|---|---|---|
| Clinker | | >55 % |
| Ground Granulated Iron Blast-Furnace Slag | Min 7.5 % | <35 % |
| Mineral Addition | | <7.5 % |
| Calcium Sulphate | | 4-8 % |
| Minor Additional Constituents | Max 5 % | <5 % |

| Reportable Property | Test Method | Requirements of AS3972 | Result |
|---|---|---|---|
| 3 Day Strength | AS/NZS2350.11 | N/R | 31.3 MPa |
| 7 Day Strength | AS/NZS2350.11 | Min 20.0 MPa | 44.4 MPa |
| 28 Day Strength | AS/NZS2350.11 | Min 35.0 MPa | 63.8 MPa |
| Initial Set Time | AS/NZS2350.4 | Min 45 min | 90 min |
| Final Set Time | AS/NZS2350.4 | Max 600 min | 165 min |
| Soundness | AS/NZS2350.5 | Max 5 mm | 1 mm |
| Sulfuric Anhydride content ($SO_3$) | AS3583.8 | Max 3.5 % | 2.6 % |
| Chloride Ion | BH-TM-0507 | Max 0.10 % | 0.037 % |
| **Other Properties** | | | |
| $SiO_2$ | AS2350.2 | N/R | 23.5 % |
| $Al_2O_3$ | AS2350.2 | N/R | 7.0 % |
| $Fe_2O_3$ | AS2350.2 | N/R | 2.4 % |
| CaO | AS2350.2 | N/R | 56.9 % |
| MgO | AS2350.2 | N/R | 3.1 % |
| $Na_2O$ Equivalent | AS2350.2 | N/R | 0.4 % |
| Loss on Ignition | AS2350.2 | N/R | 3.1 % |
| Fineness Index | AS/NZS2350.8 | N/R | 425 $m^2/kg$ |
| Normal Consistency | AS/NZS2350.3 | N/R | 30.8 % |

***This document shall not be reproduced except in full.***

**REMARKS**

These test result apply specifically to the sample as received at the Adbri Cement Birkenhead Laboratory (Accreditation number: 252), 62 Elder Rd Birkenhead SA 5015.
This despatch grab sample complies to the requirements of AS3972:2010, Type GB Cement.
N/R = No Requirement

NATA
WORLD RECOGNISED ACCREDITATION

Accredited for compliance with ISO/IEC 17025 - Testing.

Approved Signatory
M. Wythe

**Issue Date:** 07/07/2026